742

BANGALORE DIVISION.

ADVERTISEMENT.

The 7th September 1886.

Tenders are hereby invited for the restoration of Huskur Tank, Register No. 55, Nelamangala Taluk.

2. The plan and detailed estimate and conditions may be seen at the Executive Engineer's Office, Bangalore Division, between the hours of 11 A. M., and 4 P. M. daily.

3. The following is the form of tender which should be copied out and the blank columns for rates, costs and totals filled in item by item, signed by the contractors and forwarded in sealed covers to the Executive Engineer before the 22nd September 1886.

4. Form of tender—

I hereby tender for the execution of all works necessary for the restoration of the Huskur Tank, Register No. 55, Nelamangala Taluk, at the rates entered opposite to each item in the accompanying bill of quantities and in accordance with the usual sanctioned plans, conditions, &c.

Items of Work.	Per.	Quantity.	Rate.			Cost.	Total of each.	Grand Total.
			Rs.	A.	P.			
Earthwork including watering and tamping	C. yd.	9,063						
Old stonework	"	498						
New stonework	"	1,978						
Puddling	"	29						
Grade stones	No.	19						
B. M. stones	"	2						
Turfing	S. yd	382						
Brick in chunam work	C. ft.	3,149						
Slabs	S. ft.	813						
Concrete work	C. ft.	185						
New stone sujikat	C. yd.	956						
Pin stones	No.	20						
Plastering with chunam	S. qr.	12·66						
Gibbet cross and plug stones, &c., complete for each sluice.	Item. No.	2						

Signed

Contractor.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. No tender will be received unless accompanied by a deposit of Rs. 100 as earnest money.

7. Within days of the acceptance of the tender, the contractor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

8. The name of the contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

9. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicant in due course.

Note.—Huskur Tank is situated 1½ miles south-east of Gollahalli Station, S. M. Railway.

T. INMAN,
Executive Engineer.